



LEGEND

- EXISTING PARTITION TO REMAIN.
- EXISTING GLAZING TO REMAIN.
- NEW FULL HEIGHT SOLID PARTITION, 64mm STUD WITH 13mm GYPROCK EITHER SIDE WITH 50mm THICK INSULATION INTERNAL TO BE BUILT FROM FLOOR TO CEILING TILES. REFER TO PDDX.
- NEW FULL HEIGHT SOLID PARTITION, 64mm STUD WITH 2 LAYERS 13mm GYPROCK ONE SIDE AND 1 LAYER 13mm GYPROCK OTHER SIDE WITH 75mm INSULATION INTERNAL. TO BE BUILT FROM FLOOR TO CEILING TILES WITH BAFFLE BLOCK ABOVE TO UNDERSIDE OF THE SLAB. REFER TO PDDX.
- NEW FULL HEIGHT SOLID PARTITION, 64mm STUD WITH 2 LAYERS 13mm GYPROCK ONE SIDE AND 1 LAYER 13mm GYPROCK OTHER SIDE WITH 75mm INSULATION INTERNAL. TO BE BUILT FROM FLOOR TO CEILING TILES WITH BAFFLE BLOCK ABOVE TO UNDERSIDE OF THE SLAB. REFER TO PDDX.
- NEW FULL HEIGHT GLAZED PARTITION WITH 10.38mm LAMINATED GLASS. NOTE - ALLOW FOR THICKER GLASS AS REQUIRED OVER LONG GLAZED SECTIONS. ALL GLAZING TO MEET AUSTRALIAN STANDARDS. TO BE BUILT FROM FLOOR TO UNDERSIDE OF CEILING TILES WITH BAFFLE BLOCK ABOVE TO THE UNDERSIDE OF THE SLAB. 45mm x 25mm GLAZING SECTION. REFER TO PDD8.
- NEW FULL HEIGHT GLAZED PARTITION WITH 10.38mm LAMINATED GLASS. NOTE - ALLOW FOR THICKER GLASS AS REQUIRED OVER LONG GLAZED SECTIONS. ALL GLAZING TO MEET AUSTRALIAN STANDARDS. TO BE BUILT FROM FLOOR TO UNDERSIDE OF CEILING TILES WITH BAFFLE BLOCK ABOVE TO THE UNDERSIDE OF THE SLAB. WIDELINE GLAZING SECTION. REFER TO PDD8.
- INDICATES NEW ALUMINIUM FRAMED GLASS DOOR. REFER TO DOOR HARDWARE SCHEDULE FOR FURTHER DETAILS.
- INDICATES NEW SOLID DOOR. REFER TO DOOR HARDWARE SCHEDULE FOR FURTHER DETAILS
- NEW WORKSTATIONS SCREEN TYPE 1
- NEW WORKSTATION SCREEN TYPE 2
- INDICATES DOOR WITH ACCESS CONTROL
- NEW SCREEN WITH MATV.
- INDICATES NEW SCREEN WITH MATV AND VC.
- INDICATES NEW SCREEN ONLY.
- INDICATES LOCATION OF DATA PROJECTOR.
- INDICATES LOCATION OF AUTO PROJECTION SCREEN.
- INDICATES CHATBOARD PANEL TYPE 1 - 1500L x 1200H.
- INDICATES CHATBOARD PANEL TYPE 2 - 2000L x 1200H.
- INDICATES CHATBOARD PANEL TYPE 3 - 1200L x 2000H.
- GLAZING FILM TYPE 1 - REFER TO ELEVATIONS FOR DETAILS.
- GLAZING FILM TYPE 2 - REFER TO ELEVATIONS FOR DETAILS.
- GLAZING FILM TYPE 3 - REFER TO ELEVATIONS FOR DETAILS.
- GLAZING FILM TYPE 4 - REFER TO ELEVATIONS FOR DETAILS.
- INDICATES EXTENT OF CHAT BOARD INSTALLATION. TO BE SUPPLIED BY ENVOY - BUILDER TO ALLOW TO INSTALL - REFER TO ELEVATIONS FOR DETAILS.
- INDICATES EXTENT OF FEATURE PAINT COLOUR TO BE XXXX.

FURNITURE LEGEND

- INDICATES NEW WORKSTATION, SUPPLIED AND INSTALLED BY XXX.
- INDICATES NEW OFFICE FURNITURE, SUPPLIED AND INSTALLED BY XXX.
- INDICATES NEW JOINERY ITEM SUPPLIED AND INSTALLED BY HEAD CONTRACTOR.
- INDICATES NEW LOOSE FURNITURE ITEM. REFER TO NEW FURNITURE SCHEDULE FOR DETAILS.
- INDICATES EXTENT OF FEATURE PANNELLING. XXXX
- INDICATES EXTENT OF WALLPAPER INSTALLATION. XXXX
- INDICATES EXTENT OF WALLPAPER INSTALLATION. XXXX
- ALLOW FOR SUPPLY AND INSTALLATION OF AUTOMATED BLOWOUT BLINDS. TO BE XXXX
- ALLOW FOR SUPPLY AND INSTALLATION OF ROLLER BLINDS TO BE XXXX
- INDICATES EXTENT OF PINNALES. REFER TO ELEVATION FOR DETAILS.
- SHADING INDICATES EXTENT OF FLUSH PLASTERBOARD CEILING. XXXX
- EXTENT OF FLOOR FINISH TYPE 1. SHADING INDICATES EXTENT OF NEW ANTISTATIC VINYL FLOORING TO BE XXXX
- EXTENT OF FLOOR FINISH TYPE 2. ALLOW FOR NEW VINYL FLOOR FINISH. TO BE XXXX
- EXTENT OF FLOOR FINISH TYPE 2. ALLOW FOR NEW VINYL FLOOR FINISH. TO BE XXXX

GENERAL NOTES

ALL STORAGE AND LOOSE FURNITURE TO BE SUPPLIED AND INSTALLED BY OTHERS UNLESS OTHERWISE INDICATED. BUILDER TO ALLOW TO CO-ORDINATE.

BUILDER TO ALLOW TO SUPPLY AND INSTALL WHITEBOARDS IN LOCATIONS AS SHOWN. REFER TO MISCELLANEOUS SCHEDULE FOR FURTHER DETAILS.

BUILDER TO ALLOW TO SUPPLY AND INSTALL ITEMS LISTED ON MISCELLANEOUS SCHEDULE. PACKAGING TO BE DISPOSED OF.

WORKSTATIONS AND OFFICE FURNITURE TO BE SUPPLIED AND INSTALLED BY XXX. BUILDER TO ALLOW TO CO-ORDINATE AND LIASE WITH.

GENERAL NOTES

- NOTE 1** BUILDER TO ALLOW TO CO-ORDINATE LOCATIONS OF WALL MOUNTED SERVICES CONTROL PANELS TO XXX ROOMS WITH MKDC PRIOR TO INSTALLATION.
- NOTE 1** BUILDER TO ALLOW FOR ADDITIONAL STUDS AT 200mm CENTRES TO PROVIDE EXTRA SUPPORT FOR MOUNTING OF OVERHEAD STORAGE, AV ITEMS, CABINETWORK & WHITEBOARDS.
- NOTE 1** BUILDER TO ALLOW TO PAINT ALL NEW PARTITION WALLS. NEW DOORS & FLUSH PLASTERBOARD MARGINS. CORE TO REMAIN AS IS. REFER TO FINISHES SCHEDULE.
- NOTE 1** BUILDER TO ENSURE ALL NEW DOORS COMPLY WITH AS1428.1-2009 DISABLED ACCESS CODE.
- NOTE 1** BUILDER TO ALLOW FOR AFTER WORKS AS REQUIRED BY PMS MANAGEMENT FITOUT GUIDELINES.
- NOTE 1** BUILDER TO ALLOW TO INSTALL AUTO PROJECTION SCREEN AND DATA PROJECTOR (INCLUDING CEILING MOUNT BRACKET) TO XXX. LIASE WITH AV SUPPLIER TO CONFIRM EXACT LOCATION.
- NOTE 1** ALLOW TO BLANK OFF PERIMETER AIR GRILLES 500mm EITHER SIDE OF WALLS WHERE INTERSECTING WITH PERIMETER GLAZING / MULLIONS.
- NOTE 1** ALLOW FOR NIB RECESS TO SLIDING DOORS TO UTILITY AREAS AND QUIET ROOMS TO CLOSE INTO FOR GOOD ACOUSTIC SEAL.

| DATE | REV | DESCRIPTION | REASON FOR ISSUE | BY |
|----------|-----|-----------------------------------|------------------|----|
| 12.09.11 | A | ISSUE FOR BUILDING OWNER APPROVAL | | MC |
| 09.09.11 | A | ISSUE FOR CLIENT REVIEW | | MC |

| | | | |
|---|--|---|---|
| | | 803 Wellington Street, Perth, Western Australia, 6005 Telephone: (618) 9321 7955 Facsimile: (618) 9321 7111 E-mail: mkdc@mkdc.com.au Web site: www.mkdc.com.au | PROJECT NO. 11.1112 DWG NO. 004 REV NO. A |
| PROJECT CKJV OFFICE LEVEL 3, 251 ST GEORGES TERRACE PERTH WA 6000 | | TITLE FURNITURE LAYOUT PLAN LEVEL 03 | DESIGNED DRAWN CHECKED DATE SCALE 1:100 @ A1 |